

COST BREAKDOWN

Item No.	Qty	Unit	Item Description
1	1	Lump Sum	General Requirements: Payment & Performance Bonds, Insurance, NPDES Compliance Inspections, Etc.
2	1	Lump Sum	All materials, labor and equipment required for Mobilization.
3	2	Acres	Clearing and Grubbing All labor, materials, tools, equipment, and incidentals necessary to clear and grub 2 Acres, as specified on the construction drawings.
4	1	Lump Sum	Pollution Control All labor, materials, tools, equipment, and incidentals necessary to install, maintain pollution control according to Best Management Practices for the duration of the project.
5	4,930	Square Yards	4" Thick Wearing Surface Trail Reconstruction All labor, materials, tools, equipment, and incidentals necessary to install 4,930 SY of 4" thick Limerock as per FDOT Section 911 and depicted on the construction drawings.
6	4,930	Square Yards	2" Thick Sub-Base Mix All labor, materials, tools, equipment, and incidentals necessary to install 4,930 SY of 2" Thick Limerock Sub- Base Mix as per FDOT 914 and depicted on the construction drawings.
7	2,180	Square Yards	6" Thick #57 Stone Cell Fill All labor, materials, tools, equipment, and incidentals necessary to install 2,180 SY of 6" Thick #57 Stone Cell Fill as per the specification and depicted on the construction drawings.
8	2,180	Square Yards	3" Thick Wearing Surface All labor, materials, tools, equipment, and incidentals necessary to install 2,180 SY of 3" Thick Limerock as per FDOT section 911 and depicted on the construction drawings.
9	7,948	Square Yards	Geotextile Fabric All labor, materials, tools, equipment, and incidentals necessary to install 7,948 SY of Geotextile Fabric as per the specification and depicted on the construction drawings.
10	1,157	Cubic Yards	Excavation All labor, materials, tools, equipment, and incidentals necessary to excavate 1,157 CY of earth material as per the specification and depicted on the construction drawings.
11	10,867	Square Yards	Seed & Mulch All labor, materials, tools, equipment, and incidentals necessary to seed and mulch 10,867 SY of seed mix, complete in place as per the specification and depicted on the construction drawings.
12	31,240	Square Feet	6" GeoWeb Sections All labor, materials, tools, equipment, and incidentals necessary to install 31,240 SF of 6" GeoWeb Sections as per the specification and depicted on the construction drawings.

13	1	Lump Sum	As-Built Survey The Contractor shall furnish all materials, labor, equipment and incidentals necessary for As-Built Survey.
14	1	Lump Sum	Demobilization. All materials, labor and equipment required for Demobilization.

In the event that the Bidder believes that the cost of any part of the Work is not reflected in the bid item listed in the Bid Form, the cost for that part of Work should be included in a listed bid item.

BID FORM SIGNATURE'S

In witness whereof, the Bidder has hereunto set his signature and affixed his seal

this day of , A.D. 2017.

(Seal): _____

By: _____

Title: _____ **BID FORM SIGNATURE(S)**

REMAINDER OF PAGE INTENTIONALLY LEFT BLANK

Unit Price	Total Price

TOTAL BASEBID	

ms