

# FLORIDA DEPARTMENT OF TRANSPORTATION

## ADDENDUM NO. 5

DATE:4/24/2020

RE: BID/RFP #: RFP-DOT-20-1114BT

BID/RFP TITLE: District One Video Wall Solutions

OPENING DATE: June 1 ,2020 @ 10:00 a.m.

Notice is hereby given of the following changes to the above-referenced BID/RFP:

### 1. CHANGES TO RFP & SCOPE OF SERVICE:

Original:

#### I. General System Requirements

VENDOR shall provide all equipment and components necessary to establish a fully functional video wall display system.

- The system interface application shall provide full administrative control over all system configuration parameters for authorized users.
- The system interface application shall require additional login credentials independent from system user credentials.

Adds the following bullets to the end of the section:

- ***All personnel performing electrical work must be part of a state of Florida licensed company. Additionally, any personnel from the company performing electrical work for the Department must be a certified electrician.***
- ***Any electrical work must include a sign and seals plans from an Engineer for any high voltage work to include voltage drop calculations.***
- ***Any permit required shall be the Vendor's responsibility.***

Original:

#### Section III, (pg. 25 of the PDF) FDOT SWIFT SunGuide Center

- Nine (9) remote video wall display assemblies, each equipped as follows:
  - TMC Interior Hall: Two (2) 55" LED 4K flat panel display units configured in a 2 x 1 (H x W) monitor array.
  - Hallway near TMC: Two (2) 55" LED 4K flat panel display
  - Lobby: One (1) 65" LED 4K flat panel display
  - IT Area Above Datacenter: Three (3) 55" LED 4K flat panel display
  - ITS Room - 2<sup>nd</sup> Floor: One (1) 46" LCD flat panel display

**Table 1: Display Monitors to be Installed in Various Locations at the SWIFT Center**

| Display Monitor Type | Monitor Inputs                   | Designation Areas                             |
|----------------------|----------------------------------|---|
| (15) 67" LED DLP     | 4 HDMI, 1 Display Port, VGA, USB | Main Video Wall Front ( <b>Engines Only</b> ) |
| (12) 55" LED HD 4K   |                                  | Left Video Wall 1                             |
| (12) 55" LED HD 4K   |                                  | Left Video Wall 2                             |
| (6) 55" LED HD 4K    |                                  | Right Video Wall 1                            |
| (6) 55" LED HD 4K    |                                  | Right Video Wall 2                            |
| (2) 55" LED HD 4K    | 2 HDMI, 1 Display Port, VGA, USB | TMC Interior Hall (TMC Vestibule)             |
| (2) 55" LED HD 4K    |                                  | Hallway near TMC                              |
| (1) 65" LED HD 4K    |                                  | Lobby Area                                    |
| (3) 55" LED HD 4K    |                                  | IT Area Above Datacenter                      |
| (1) 46" LED HD 4K    |                                  | Right by the cubicle areas                    |

FDOT D1 HQ Remote Site

**Table 2: Display Monitors to be Installed in Various Locations at the FDOT D1 HQ**

| Display Monitor Type | Monitor Inputs                   | Designation Areas                       |
|----------------------|----------------------------------|---|
| (1) 55" LED HD 4K    | 4 HDMI, 1 Display Port, VGA, USB | Lobby 1 <sup>st</sup> Floor (Existing)  |
| (2) 55" LED HD 4K    |                                  | New EOC Room (New)                      |
| (1) 55" LED HD 4K    |                                  | Construction Conference Room (Existing) |
| (1) 65" LED HD 4K    |                                  | Executive Office (Existing)             |
| (2) 80" LED HD 4K    |                                  | TSMO Planning Area (New)                |
| (3) 55" LED HD 4K    |                                  | TSMO Area (New)                         |

To be replaced with the following:

**Section III, (pg. 25 of the PDF) FDOT SWIFT SunGuide Center**

- Nine (9) remote video wall display assemblies, each equipped as follows:
  - TMC Interior Hall: Two (2) 55" LED 4K flat panel display units configured in a 2 x 1 (H x W) monitor array.
  - Hallway near TMC: Two (2) 55" LED 4K flat panel display
  - Lobby: One (1) 65" LED 4K flat panel display
  - IT Area Above Datacenter: Three (3) 55" LED 4K flat panel display
  - ITS Room - 2<sup>nd</sup> Floor: One (1) 46" 4K flat panel display

**Table 1: Display Monitors to be Installed in Various Locations at the SWIFT Center**

| Display Monitor Type | Monitor Inputs | Designation Areas |
|----------------------|----------------|-------------------|
|----------------------|----------------|-------------------|

|                |               |   |
|----------------|---------------|---|
| (15) 67" DLP   | 4 HDMI, 1 USB | Main Video Wall Front ( <b>Engines Only</b> ) |
| (12) 55" HD 4K |               | Left Video Wall 1                             |
| (12) 55" HD 4K |               | Left Video Wall 2                             |
| (6) 55" HD 4K  |               | Right Video Wall 1                            |
| (6) 55" HD 4K  |               | Right Video Wall 2                            |
| (2) 55" HD 4K  | 2 HDMI, 1 USB | TMC Interior Hall (TMC Vestibule)             |
| (2) 55" LED 4K |               | Hallway near TMC                              |
| (1) 65" LED 4K |               | Lobby Area                                    |
| (3) 55" LED 4K |               | IT Area Above Datacenter                      |
| (1) 46" LED 4K |               | Right by the cubicle areas                    |

FDOT D1 HQ Remote Site

**Table 2: Display Monitors to be Installed in Various Locations at the FDOT D1 HQ**

| Display Monitor Type | Monitor Inputs | Designation Areas                       |
|----------------------|----------------|---|
| (1) 55" HD 4K        | 4 HDMI, 1 USB  | Lobby 1 <sup>st</sup> Floor (Existing)  |
| (2) 55" HD 4K        |                | New EOC Room (New)                      |
| (1) 55" HD 4K        |                | Construction Conference Room (Existing) |
| (1) 65" HD 4K        |                | Executive Office (Existing)             |
| (2) 80" HD 4K        |                | TSMO Planning Area (New)                |
| (3) 55" HD 4K        |                | TSMO Area (New)                         |

Original:

**Special Conditions Questions**

**22.2.3 Deployment Plan & Project Schedule (pg.17 of the PDF) –**

1. DEPLOYMENT PLAN & PROJECT SCHEDULE (**Maximum of 2 pages, 30 Points**)

The Proposer shall provide a realistic schedule and plan to deploy the proposed solution required for this project. The Proposer shall provide a plan which sets forth the project schedule along with the sequence of the work to be performed under the scope of services. The Proposer should plan to start work on or about March 1, 2020 and complete services no later than July 15, 2020. At minimum, the schedule shall reflect all major milestones and activities with durations, logical ties and float. The Project Schedule shall be printable on 11x17 size pages. The Proposer shall limit the Deployment Plan & Project Schedule to no more than two (2) pages.

To be replaced with:  
**Special Conditions Questions**

**22.2.3 Deployment Plan & Project Schedule (pg.17 of the PDF) –**

1. DEPLOYMENT PLAN & PROJECT SCHEDULE (**Maximum of 2 pages, 30 Points**)

The Proposer shall provide a realistic schedule and plan to deploy the proposed solution required for this project. The Proposer shall provide a plan which sets forth the project schedule along with the sequence of the work to be performed under the scope of services. The Proposer should plan to start work on or about **July 1, 2020 and complete services no later than November 15, 2020**. At minimum, the schedule shall reflect all major milestones and activities with durations, logical ties and float. The Project Schedule shall be printable on 11x17 size pages. The Proposer shall limit the Deployment Plan & Project Schedule to no more than two (2) pages.

**Bidders/Proposers must acknowledge receipt** of this Addendum by completing and returning to the Procurement Office, by no later than the time and date of the bid/proposal opening. **Failure to do so may subject the bidder/proposer to disqualification.**

Belinda M.Thomas  
Procurement Agent

\_\_\_\_\_ Bidder/Proposer

\_\_\_\_\_ Address

\_\_\_\_\_  
Submitted by (Signature)

Failure to file a protest within the time prescribed in Section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under Chapter 120, Florida Statutes.