

**New Security Fencing and New Electric Slide Security Gate for Bay County
Detention Center - Scope of Work**

- Provide all materials and labor for the installation of Security Fencing and a Sliding Security Gate as indicated below:
 - Provide and install approximately 211 feet of 14' high straight galvanized chain link fence
 - 9-gauge chain link fabric fence
 - 4" SS-40 Line Posts located at 10+/- feet apart
 - 4" SS-40 Terminal Posts
 - 1 5/8" SS-40 Gauge rails (3 rails- 1 each - top, middle and bottom)
 - Secure all 9-gauge chain link fence fabric to all line post, terminal post and rails with 9- gauge wire ties
 - 4' of ¼" Non-Climb Hardware Cloth secured at top of fence line
 - Provide and install (1) 5' wide walk gate, location as indicated by Owner
 - Provide and install (1) 16' slide gate with HySecurity Slide Driver Operator, Provide Telephone/Intercom (location as indicated by Owner), Free Exit Loops, All High and Low Voltage Wiring (approximately 200') and conduits, connected back to Master Control Room.
 - All Post set in 12"wide X 48"deep Concrete footings.

Project Title: New Security Fencing and New Electric Slide Security Gate for Bay County Detention Center

Project Location: 450 East 11th Street, Panama City, Florida

Project Contact: Darrell Phillips, Construction Project Manager II, Office phone 850-717-2758, Cell Number 850-251-0726