



**MEMORANDUM
ADDENDUM NO. 1**

Date: April 19, 2021

To: Bidders

From: Robin Morgan
Senior Contract Specialist
Florida's Turnpike Enterprise

Subject: DOT-ITB-21-8022-RM
Replacement of Emergency Standby Generators, Fuel Tanks and Automatic Transfer Switches (ATS)
at various locations along the Florida's Turnpike system – North Region

Bidders and other interested parties are informed that the referenced document is hereby revised changed and supplemented as set forth below:

- Attachment C – Scope of Services and General Requirements - Page 2 of 48.

Please replace the above referenced page in the Complete Bid Package with the attached revised page, dated 4/19/2021.

Failure to file a protest within the time prescribed in Section 120.57(3), Florida Statutes, or failure to post the bond or other security required by law within the time allowed for filing a bond shall constitute a waiver of proceedings under Chapter 120, Florida Statutes.

ATTACHMENT "C"

SCOPE OF SERVICES AND GENERAL REQUIREMENTS

- The Vendor shall install new LP line and ground the tank.
 - Fill the new 1,000-gallon LP tank with fuel to 80% full.
 - There is an existing surge suppression system which is to remain and incorporated as part of the new work.
 - There are two existing remote alarms for utility power and generator run that are to be reestablished in the new ATS. Provide the necessary alarm terminations or relays. Proper operation of the remote alarms shall be demonstrated to the Contract Manager prior to final acceptance.
- 2) **CR-470 N/B Ramp Toll Plaza, Building 5959, SR 91 MP 296.0**
- The Vendor shall remove and dispose of the existing standby generator and ATS.
 - The Vendor shall furnish and install new outdoor Liquid Propane (LP), 50 KW 120/240 volts single phase standby generator.
 - The Vendor shall furnish and install new 150 AMP single phase ATS unit.
 - The Vendor shall install new propane regulators in accordance with the generator's factory specifications.
 - ~~The Vendor shall fill new tank with fuel to 85% full.~~
- 3) **CR-470 S/B Ramp Toll Plaza, Building 5961, SR 91, MP 296.0**
- The Vendor shall remove and dispose of the existing standby generator and ATS.
 - The Vendor shall furnish and install new outdoor Liquid Propane (LP), 50 KW 120/240 volts single phase standby generator.
 - The Vendor shall furnish and install new 150 AMP single phase ATS unit.
 - The Vendor shall install new propane regulators in accordance with the generator's factory specifications.
 - ~~The Vendor shall fill new tank with fuel to 85% full.~~
- 4) **Aloma Avenue S/B Ramp Toll Plaza, Building 5464, SR 417, MP 38.0**
- The Vendor shall remove and dispose of the existing standby generator and ATS.
 - The Vendor shall furnish and install new outdoor Liquid Propane (LP), 22 KW 120/240 volts single phase standby generator.
 - The Vendor shall furnish and install new 400 AMP single phase ATS unit.
 - The Vendor shall install new propane regulators in accordance with the generator's factory specifications.
 - ~~The Vendor shall fill new tank with fuel to 85% full.~~